

ENVIRONMENTAL
CLEARANCE



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), Maharashtra)

To,

The PARTNER
GOLDFINGER KATARIA URBAN DEVELOPMENTS
S. No.: 48/4-10, Rahatani, Pune -411017

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/MIS/243759/2021 dated 08 Dec 2021. The particulars of the environmental clearance granted to the project are as below.

- | | |
|--|---|
| 1. EC Identification No. | EC22B038MH110494 |
| 2. File No. | SIA/MH/MIS/243759/2021 |
| 3. Project Type | New |
| 4. Category | B2 |
| 5. Project/Activity including Schedule No. | 8(a) Building and Construction projects |
| 6. Name of Project | TAMARA |
| 7. Name of Company/Organization | GOLDFINGER KATARIA URBAN DEVELOPMENTS |
| 8. Location of Project | Maharashtra |
| 9. TOR Date | N/A |

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 01/06/2022

(e-signed)
Manisha Patankar Mhaiskar
Member Secretary
SEIAA - (Maharashtra)

Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH. Please quote identification number in all future correspondence.

This is a computer generated cover page.

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive,
and Virtuous Environmental Single-Window Hub)



STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/MIS/243759/2021
 Environment & Climate
 Change Department
 Room No. 217, 2nd Floor,
 Mantralaya, Mumbai- 400032.

To
 Mr. Kumar Kataria,
 S. No. 48/4-10, Rahatani,
 Haveli, Pune.

Subject : Environment Clearance for Proposed construction project TAMARA at
 S. No. 48/4-10, Rahatani, Haveli, Pune by Mr. Kumar Kataria

Reference : Application no. SIA/MH/MIS/243759/2021

This has reference to your communication on the above mentioned subject. The proposal was considered by the SEAC-3 in its 106th & 135th meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 197th & 242nd (Day-4) meeting of State Level Environment Impact Assessment Authority (SEIAA).

2. Brief Information of the project submitted by you is as below:-

Sr. No.	Particular	Details
1	Proposal Number	SIA/MH/MIS/243759/2021
2	Name of Project	Proposed Residential & Commercial Project "TAMARA"
3	Project category	B Category, 8(a)
4	Type of Institution	Private
5	Project Proponent	<ul style="list-style-type: none"> Name: Mr. Kumar Kataria Address: C1101, Park Tatiniium, C Building, Park Street, Near Wisdom World School, Wakad, Pune Phone No: --
6	Name of Consultant	<ul style="list-style-type: none"> Name: Building Environment (India) Pvt. Ltd. NABET Accreditation No.: NABET/EIA/1922/SA 0136 Validity: 27/05/2022
7	Applied for	Fresh EC
8	Details of Previous EC	NA
9	Location of the project	S. No. 48/4-10, Rahatani, Haveli, Pune
10	Latitude and Longitude	--
11	Total Plot Area	12700.0 Sq.M..
12	Deductions	1390.86 Sq.M.
13	Net Plot Area	11309.14 Sq.M.
14	Proposed FSI area	19660.36 Sq.M.
15	Proposed Non FSI area	19593.46 Sq.M.

16	Proposed Total Built up Area	39253.82 Sq.M.																					
17	Total Built up area approved by Planning Authority	23613.64 Sq.M.																					
18	Ground Coverage	2126.43 Sq.m.																					
19	Total Project Cost	Rs. 105.0 Cr.																					
20	CER as per MoEF & CC circular dated 01/05/2018	CER Shall be Implemented as a part of EMP as recommended by SEAC/SEIAA as mentioned in OM F. No. 22-65/2017-IA.III dated 30 September, 2020 and OM file No. 22-65/2017-IA.III dated 25/02/2021.																					
21	Details of Building Configuration	<p>Proposed Building Configuration:</p> <table border="1"> <thead> <tr> <th>Building Name</th> <th>Configuration</th> <th>Height</th> </tr> </thead> <tbody> <tr> <td>Building. A</td> <td>LP+UP+11 FL</td> <td>39 m</td> </tr> <tr> <td>Building. B</td> <td>LP+UP+11 FL</td> <td>39 m</td> </tr> <tr> <td>Building. C</td> <td>LP+UP+11 FL</td> <td>39 m</td> </tr> <tr> <td>Building. D</td> <td>LP+UP+11 FL</td> <td>39 m</td> </tr> <tr> <td>Building. E</td> <td>LP+UP+11 FL</td> <td>39 m</td> </tr> <tr> <td>Commercial Building</td> <td>G+7</td> <td>21</td> </tr> </tbody> </table>	Building Name	Configuration	Height	Building. A	LP+UP+11 FL	39 m	Building. B	LP+UP+11 FL	39 m	Building. C	LP+UP+11 FL	39 m	Building. D	LP+UP+11 FL	39 m	Building. E	LP+UP+11 FL	39 m	Commercial Building	G+7	21
Building Name	Configuration	Height																					
Building. A	LP+UP+11 FL	39 m																					
Building. B	LP+UP+11 FL	39 m																					
Building. C	LP+UP+11 FL	39 m																					
Building. D	LP+UP+11 FL	39 m																					
Building. E	LP+UP+11 FL	39 m																					
Commercial Building	G+7	21																					
22	Total number of tenements	<p>Tenements: 215 Nos. Shops: 14 Nos.& Offices- 98 Nos</p> <p>Residential Users:1075 Nos., Commercial Users: 533 Nos., Total Users: 1608 Nos.</p>																					
23	Water Budget	<p>Proposed water budget</p> <table border="1"> <thead> <tr> <th>Particular</th> <th>Dry Season</th> <th>Wet Season</th> </tr> </thead> <tbody> <tr> <td>Fresh Water</td> <td>178.49 KLD</td> <td>168.49 KLD</td> </tr> <tr> <td>Recycled (Flushing)</td> <td>61.71 KLD</td> <td>61.71 KLD</td> </tr> <tr> <td>Recycled (Landscape)</td> <td>10 KLD</td> <td>0 KLD</td> </tr> <tr> <td>Swimming Pool</td> <td>2.03 KLD</td> <td>2.03 KLD</td> </tr> <tr> <td>Total Water Requirement</td> <td>106.78 KLD</td> <td>106.78 KLD</td> </tr> <tr> <td>Waste water generation</td> <td>149.79 KLD</td> <td>149.79 KLD</td> </tr> </tbody> </table>	Particular	Dry Season	Wet Season	Fresh Water	178.49 KLD	168.49 KLD	Recycled (Flushing)	61.71 KLD	61.71 KLD	Recycled (Landscape)	10 KLD	0 KLD	Swimming Pool	2.03 KLD	2.03 KLD	Total Water Requirement	106.78 KLD	106.78 KLD	Waste water generation	149.79 KLD	149.79 KLD
Particular	Dry Season	Wet Season																					
Fresh Water	178.49 KLD	168.49 KLD																					
Recycled (Flushing)	61.71 KLD	61.71 KLD																					
Recycled (Landscape)	10 KLD	0 KLD																					
Swimming Pool	2.03 KLD	2.03 KLD																					
Total Water Requirement	106.78 KLD	106.78 KLD																					
Waste water generation	149.79 KLD	149.79 KLD																					
24	Water Storage Capacity for Fire Fighting/ UGT	<p>One UGT proposed: Details as follows</p> <p>UGT: Domestic UG tank Capacity :175 m³ Flushing Water Tank : 40 m³ Fire UG tank Capacity : 250 m³</p>																					
25	Source of Water	<p>Pimpri-Chinchwad Municipal Corporation (PCMC)</p> <p>STP treated water will be reused for flushing & landscape purpose.</p>																					
26	Rainwater Harvesting (RWH)	<ul style="list-style-type: none"> Level of Ground Water Table: 15 m BGL Size & No. of RWH tanks and Quantity: NA Quantity and size of recharge pits: 5 nos of recharge pits proposed 2.0 m x 2.0m x 1.5 m. 																					

		<p>UGT:</p> <ul style="list-style-type: none"> • Located below ramp • Drinking UG tank Capacity: 24 Cu.M. • Domestic UG tank Capacity: 151 Cu.M. • Fire UG tank Capacity: 150 Cu.M. 																		
27	Sewage and Wastewater	<ul style="list-style-type: none"> • Sewage Generation: 149.79 KLD • Proposed STP Capacity: Total 150 KLD Capacity • STP Technology: MBBR 																		
28	Solid waste management during construction phase	<table border="1"> <thead> <tr> <th>Type</th> <th>Quantity</th> <th>Treatment/ disposal</th> </tr> </thead> <tbody> <tr> <td>Dry waste</td> <td>Negligible</td> <td>Collect & disposed through authorized agency.</td> </tr> <tr> <td>Wet waste</td> <td>Negligible</td> <td>Provision of composting</td> </tr> <tr> <td>Construction waste</td> <td>Top Soil & Debris</td> <td>Top soil will be reused for landscape purpose within project site. Excavated debris will be will be reused for backfilling, levelling & plinth filling purpose.</td> </tr> </tbody> </table>	Type	Quantity	Treatment/ disposal	Dry waste	Negligible	Collect & disposed through authorized agency.	Wet waste	Negligible	Provision of composting	Construction waste	Top Soil & Debris	Top soil will be reused for landscape purpose within project site. Excavated debris will be will be reused for backfilling, levelling & plinth filling purpose.						
Type	Quantity	Treatment/ disposal																		
Dry waste	Negligible	Collect & disposed through authorized agency.																		
Wet waste	Negligible	Provision of composting																		
Construction waste	Top Soil & Debris	Top soil will be reused for landscape purpose within project site. Excavated debris will be will be reused for backfilling, levelling & plinth filling purpose.																		
29	Solid waste management during operation phase	<table border="1"> <thead> <tr> <th>Type</th> <th>Quantity</th> <th>Treatment/ disposal</th> </tr> </thead> <tbody> <tr> <td>Dry waste</td> <td>294.95 Kg/day</td> <td>Will be collected & disposed by SWaCH Organization</td> </tr> <tr> <td>Wet waste</td> <td>375.80 Kg/day</td> <td>Treated in Smart Drum Organic waste composter and used as manure in landscape</td> </tr> <tr> <td>Hazardous waste</td> <td>--</td> <td>NA</td> </tr> <tr> <td>Biomedical waste</td> <td>--</td> <td>NA</td> </tr> <tr> <td>STP Sludge</td> <td>13.48 Kg/day</td> <td>Treated in OWC and used as manure in landscape</td> </tr> </tbody> </table>	Type	Quantity	Treatment/ disposal	Dry waste	294.95 Kg/day	Will be collected & disposed by SWaCH Organization	Wet waste	375.80 Kg/day	Treated in Smart Drum Organic waste composter and used as manure in landscape	Hazardous waste	--	NA	Biomedical waste	--	NA	STP Sludge	13.48 Kg/day	Treated in OWC and used as manure in landscape
Type	Quantity	Treatment/ disposal																		
Dry waste	294.95 Kg/day	Will be collected & disposed by SWaCH Organization																		
Wet waste	375.80 Kg/day	Treated in Smart Drum Organic waste composter and used as manure in landscape																		
Hazardous waste	--	NA																		
Biomedical waste	--	NA																		
STP Sludge	13.48 Kg/day	Treated in OWC and used as manure in landscape																		
30	Green Belt Development	<ul style="list-style-type: none"> • Total Green Area: 1262.33 Sq.M. • Existing trees on Plot: 0 • Number of trees to be plant: 194 Nos. • Number of trees to be cut: 0 • Number of trees to be transplant: 0 																		
31	Power Requirement	<ul style="list-style-type: none"> • Source of power supply: MSEDCL • During Construction Phase (Demand Load): 75 kW • During Operation Phase (Connected Load): 1770.0 kW • During Operation Phase (Demand Load): 1070.0 kW • Transformer: 2 x 630 kVA capacity • DG Set: 01No. x 200 KVA (Residential), 01No. x 62.5 KVA (Commercial) • Fuel Used: HSD - 45.4 lit/hr (DG Set 200 KVA: 34.4 lit/hr. & DG Set 62.5 KVA :11 lit/hr.) 																		

32	Details of Energy Saving	<ul style="list-style-type: none"> • Auto Timer control for external & common lighting. • Use of LED lamps in all public/ common areas. • Solar PV Energy for Common Area Lighting. • Solar powered water heating. • Electronic V3F Drives for Elevators <table border="1" data-bbox="635 405 1433 663"> <thead> <tr> <th>Energy Conservation Measures</th> <th>Saving %</th> </tr> </thead> <tbody> <tr> <td>Solar PV Energy</td> <td>10125 KWH / Annum</td> </tr> <tr> <td>Timer Logic Controller</td> <td>19622 KWH / Annum</td> </tr> <tr> <td>Electronic VVF drive for Lifts</td> <td>14704 KWH / Annum</td> </tr> <tr> <td>Solar Water Heater</td> <td>299280 KWH / Annum</td> </tr> </tbody> </table>	Energy Conservation Measures	Saving %	Solar PV Energy	10125 KWH / Annum	Timer Logic Controller	19622 KWH / Annum	Electronic VVF drive for Lifts	14704 KWH / Annum	Solar Water Heater	299280 KWH / Annum																																													
Energy Conservation Measures	Saving %																																																								
Solar PV Energy	10125 KWH / Annum																																																								
Timer Logic Controller	19622 KWH / Annum																																																								
Electronic VVF drive for Lifts	14704 KWH / Annum																																																								
Solar Water Heater	299280 KWH / Annum																																																								
33	Environment Management Plan during Construction phase	<table border="1" data-bbox="635 696 1414 1200"> <thead> <tr> <th>Sr. No.</th> <th>Parameter</th> <th>Capital Cost (Rs. In Lakh/Year)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>Water for Dust Suppression, Air & Noise Monitoring</td> <td>0.50</td> </tr> <tr> <td>2</td> <td>Tanker Water for Construction, Water Monitoring</td> <td>0.50</td> </tr> <tr> <td>3</td> <td>Site Sanitation –Mobile toilets</td> <td>0.50</td> </tr> <tr> <td>4</td> <td>Disinfection- Pest Control, First Aid Facilities, Health Check Up, Creches For Children, Food for children, Personal Protective Equipment</td> <td>1.0</td> </tr> <tr> <td colspan="2">TOTAL</td> <td>2.50</td> </tr> </tbody> </table>	Sr. No.	Parameter	Capital Cost (Rs. In Lakh/Year)	1	Water for Dust Suppression, Air & Noise Monitoring	0.50	2	Tanker Water for Construction, Water Monitoring	0.50	3	Site Sanitation –Mobile toilets	0.50	4	Disinfection- Pest Control, First Aid Facilities, Health Check Up, Creches For Children, Food for children, Personal Protective Equipment	1.0	TOTAL		2.50																																					
Sr. No.	Parameter	Capital Cost (Rs. In Lakh/Year)																																																							
1	Water for Dust Suppression, Air & Noise Monitoring	0.50																																																							
2	Tanker Water for Construction, Water Monitoring	0.50																																																							
3	Site Sanitation –Mobile toilets	0.50																																																							
4	Disinfection- Pest Control, First Aid Facilities, Health Check Up, Creches For Children, Food for children, Personal Protective Equipment	1.0																																																							
TOTAL		2.50																																																							
34	Environment Management Plan Operation phase	<table border="1" data-bbox="635 1234 1433 1890"> <thead> <tr> <th>Sr. No.</th> <th>Component</th> <th>Details</th> <th>Capital Cost (Rs. Lakh)</th> <th>O &M Cost (Rs. Lakh)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>STP</td> <td>Capacity - 150 KLD</td> <td>21.00</td> <td>4.80</td> </tr> <tr> <td>2</td> <td>RWH</td> <td>--</td> <td>3.50</td> <td>1.20</td> </tr> <tr> <td>3</td> <td>MSW</td> <td>--</td> <td>11.75</td> <td>2.90</td> </tr> <tr> <td>4</td> <td>Solar System</td> <td>--</td> <td>54.00</td> <td>2.10</td> </tr> <tr> <td>5</td> <td>Landscaping</td> <td>--</td> <td>12.00</td> <td>1.00</td> </tr> <tr> <td>6</td> <td>Swimming Pool</td> <td>--</td> <td>4.90</td> <td>1.80</td> </tr> <tr> <td>7</td> <td>Safety Equipments</td> <td>--</td> <td>10.00</td> <td>2.00</td> </tr> <tr> <td>8</td> <td>Post EC Monitoring</td> <td>--</td> <td></td> <td>2.50</td> </tr> <tr> <td>9</td> <td>Dry Waste management</td> <td>--</td> <td></td> <td>1.29</td> </tr> <tr> <td colspan="3">TOTAL</td> <td>117.15</td> <td>19.59</td> </tr> </tbody> </table>	Sr. No.	Component	Details	Capital Cost (Rs. Lakh)	O &M Cost (Rs. Lakh)	1	STP	Capacity - 150 KLD	21.00	4.80	2	RWH	--	3.50	1.20	3	MSW	--	11.75	2.90	4	Solar System	--	54.00	2.10	5	Landscaping	--	12.00	1.00	6	Swimming Pool	--	4.90	1.80	7	Safety Equipments	--	10.00	2.00	8	Post EC Monitoring	--		2.50	9	Dry Waste management	--		1.29	TOTAL			117.15	19.59
Sr. No.	Component	Details	Capital Cost (Rs. Lakh)	O &M Cost (Rs. Lakh)																																																					
1	STP	Capacity - 150 KLD	21.00	4.80																																																					
2	RWH	--	3.50	1.20																																																					
3	MSW	--	11.75	2.90																																																					
4	Solar System	--	54.00	2.10																																																					
5	Landscaping	--	12.00	1.00																																																					
6	Swimming Pool	--	4.90	1.80																																																					
7	Safety Equipments	--	10.00	2.00																																																					
8	Post EC Monitoring	--		2.50																																																					
9	Dry Waste management	--		1.29																																																					
TOTAL			117.15	19.59																																																					
35	Traffic Management	<table border="1" data-bbox="635 1924 1433 2031"> <thead> <tr> <th>Type</th> <th>Required as per DCR</th> <th>Actual Provided</th> <th>Area per Parking</th> </tr> </thead> <tbody> <tr> <td>4-Wheeler</td> <td>210 No.</td> <td>210 No.</td> <td>--</td> </tr> </tbody> </table>	Type	Required as per DCR	Actual Provided	Area per Parking	4-Wheeler	210 No.	210 No.	--																																															
Type	Required as per DCR	Actual Provided	Area per Parking																																																						
4-Wheeler	210 No.	210 No.	--																																																						

		2-Wheeler	625 No.	625 No.	--
		Total Parking Area: 8875.0 Sq.M.			
36	Details of Court Cases/ litigations w.r.t. the project and project location if any	NA			

3. Proposal is a violation of EIA Notification, 2006. PP has applied within the amnesty period as per MoEF&CC Notification dated 14th March 2017 & 8th March 2018. Proposal has been considered by SEIAA in its 197th & 242nd (Day-4) meeting and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. The committee noted that Cost of remediation plan and natural & community resource augmentation plan as per revised approach paper is estimated as Rs. 2.05 Cr. The Committee also noted that the amount of CER as per MoEF & CC circular dated 1/05/2018 is Rs. 0.45 Cr which is less than the remediation / augmentation plan. Therefore committee decided to obtain Bank Guarantee of Rs 2.05 Cr for the project completion period.
2. PP to submit Revised RG plan by shifting plants located at STP, OWC and UGT.

B. SEIAA Conditions-

1. PP has submitted bank guarantee of Rs.205 lakhs (Rs.2.05 Crores) to Maharashtra Pollution Control Board towards effective implementation of the EMP comprising remediation plan and Natural and Community Resource augmentation Plan. PP to complete implementation of the EMP comprising remediation plan and Natural and Community Resource augmentation Plan within 1 year of grant of Environment Clearance.
2. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
3. The Authority accepted the calculations submitted by PP and decided to grant EC for – FSI: 19579.35 m2, Non-FSI: 19674.47 m2 and Total BUA: 39253.82 m2 (Plan Approval no- BP/EC/Rahatani/03/2020, dtd.09.03.2020)

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.

- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all

- proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely

circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at <http://parivesh.nic.in>

- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC & SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies

that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.
8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.


Manisha Patankar, Maishkar
(Member Secretary, SEIAA) 20/5/2022

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Pune.
6. Commissioner, Pimpri Chinchwad Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Pune.

